

## Standard Cast Pipeline Strainers



Partial cutaway of plug type duplex strainer showing basket in position




Cutaway of Y strainer shows strainer screen in position



Cone type temporary strainer is shown bolted between two pipe flanges

## **Basic Sizing Guidelines**

- 1. Ensure that the pipeline flow velocity falls within the standard design range of the strainer.
- 2. Select the correct screen and opening size, do not make smaller than necessary.
- 3. The quantity, type, and nature of debris to be removed are considered.
- 4. The strainer meets the design pressure and temperature requirements of the pipeline.







Threaded or Flanged

## **FEATURES**

- Quick open cover—no tools needed
- Heavy wall construction
- Large capacity baskets
- Machined basket seat
- Threaded drain
- Perforated or mesh 316 stainless basket
- Mounting feet for stable installation for flanged units 2" and larger

## OPTIONS

- Basket perforations from 1/32" to 1/2"
- Basket mesh from 20 to 400
- Monel baskets
- Viton, PTFE-encapsulated, or EPDM seals
- Vent valves
- Gauge/vent taps 1/4" NPT
- Magnetic basket inserts
- Pressure differential gauge and switch

The Eaton Model 72 has been the industry standard simplex basket strainer for more than 75 years. It is perfect for industrial and commercial applications in which the line can be temporarily shut down for strainer basket cleaning or changeout.

A reason for its popularity is the unusually large basket capacity. The free straining area with a perforated basket is a minimum of six times the cross sectional pipe area. No tools are needed to open the cover. The quick opening, swinging yoke can be disassembled and the basket removed in seconds. On sizes 4" and larger, a special cover clamp is provided to distribute

the seating pressure and to ensure positive seating of the cover.

Another feature is a threaded drain on every size strainer (fitted with a plug). Sizes 2" and larger are equipped with legs that bolt to the floor for rock solid installation.


Wall thicknesses are exceptionally heavy. The basket seats are precision machined to give a tight seal and prevent any material from bypassing the basket. The Eaton Model 72 simplex basket strainer is a top quality, heavy-duty unit designed to stand up to the most demanding of applications.


#### Model 72 Simplex

Size	Material	<b>End Connection</b>	Seals	Pressure Rating
3/8" to 3"	Iron and Bronze	Threaded	Buna-N	200 psi @ 100°F
1" to 3"	Carbon Steel	Threaded	Buna-N	200 psi @ 100°F
1" to 3"	Stainless Steel	Threaded	Viton®	200 psi @ 100°F
1" to 8"	Iron	Flanged 125#	Buna-N	200 psi @ 100°F
1" to 8"	Bronze	Flanged 150#	Buna-N	200 psi @ 100°F
1" to 8"	Carbon Steel	Flanged 150#	Buna-N	200 psi @ 100°F
1" to 8"	Stainless Steel	Flanged 150#	Viton®	200 psi @ 100°F

Click Here
For Your Free Quote

## **MODEL 72 Simplex Basket Strainer**





Threaded Model 72 Dimensions (in/mm)

Dimensions and weights are for reference only. Contact Eaton for certified drawings.

										·····Net Wt	(lbs / kg)	Stainless
Size	A	В	C	D	E	F	G	Н	Bronze	Steel	Iron	Steel
3/8	4.00 / 102	6.63 / 168	2.88 / 73	4.00 / 102	2.38 / 60	-	3/8	11 / 279	4 / 1.8	-	4 / 1.8	-
1/2	4.00 / 102	6.63 / 168	2.88 / 73	4.00 / 102	2.38 / 60	-	3/8	11 / 279	4 / 1.8	-	4 / 1.8	-
3/4	5.38 / 137	8.38 / <mark>213</mark>	4.00 / 102	5.00 / 127	3.06 / 78	-	1/2	13 / 330	8 / 3.6	-	7 / 3.2	-
1	5.38 / 137	8.38 / <mark>213</mark>	4.00 / 102	5.00 / 127	3.06 / 78	-	1/2	13 / 330	8 / 3.6	7 / 3.2	7 / 3.2	7 / 3.2
1-1/4	6.75 / 172	9.88 / <mark>251</mark>	4.88 / 124	5.88 / 149	3.88 / 99	-	1/2	14 / 356	13 / 6	-	12 / 6	-
1-1/2	7.25 / 184	11.00 / 279	4.88 / 124	7.00 / 178	4.00 / 102	-	3/4	16 / <del>406</del>	16 / <mark>7</mark>	15 / <mark>7</mark>	15 / <mark>7</mark>	16 / 7.3
2	8.75 / <mark>222</mark>	13.38 / 340	6.75 / 172	7.63 / 194	5.13 / 130	-	1-1/4	21 / 533	32 / <mark>15</mark>	36 / <mark>16</mark>	28 / 13	31 / 14
2-1/2	10.38 / 264	14.88 / 378	8.00 / <mark>203</mark>	8.63 / <b>219</b>	6.38 / 162	-	1-1/2	26 / 660	49 / <mark>22</mark>	52 / <mark>24</mark>	42 / 19	51 / <mark>23</mark>
3	11.50 / <mark>292</mark>	17.75 / <mark>468</mark>	8.00 / <mark>203</mark>	11.38 / <mark>298</mark>	6.63 / 168	-	1-1/2	28 / <mark>711</mark>	60 / <mark>27</mark>	60 / <mark>27</mark>	52 / <mark>23</mark>	60 / <mark>27</mark>

Mod.	72C <sub>v</sub>	Fact	ors*
Size	Value	Size	Value
3/8"	15.0	2"	73
1/2"	15.0	2-1/2"	125
3/4"	15.0	3"	180
1"	22.5	4"	350
1-1/4"	31.5	6"	900
1_1/_"	46 N	Ω"	1/100

<sup>\*</sup> For water with clean, perforated basket

## Flanged Model 72 Dimensions (in/mm)

										Net Wt (lbs / kg	)	
Size	Α	В	С	D	E	F	G	Н	Bronze	Carbon Steel	Iron	Stainless Steel
1	7.63 / 194	8.38 / 213	4.00 / 102	5.00 / 127	_	-	1/2	13.00 / 330	16 / 7	9 / 4	9 / 4	9 / 4
1-1/2	10.25 / 260	11.00 / 279	4.88 / 124	7.00 / 178	_	-	3/4	16.00 / 406	30 / 14	17 / 7.7	17 / 7.7	17 / 7.7
2	10.50 / <mark>268</mark>	13.75 / 349	6.75 / 172	7.63 / 194	5.13 / 130	6.25 / 159	3/8	20.00 / 508	49 / 22.3	36 / 16	36.5 / 17	36 / 16
2-1/2	11.63 / 295	15.63 / 397	8.00 / <del>203</del>	8.88 / <mark>226</mark>	6.38 / 162	7.63 / 194	3/8	23.00 / 584	64 / <mark>29.1</mark>	63 / <mark>27</mark>	54 / <mark>25</mark>	63 / <mark>29</mark>
3	13.13 / 334	18.00 / <b>457</b>	8.00 / <mark>203</mark>	10.63 / 270	6.50 / 165	8.00 / <del>203</del>	3/8	27.00 / 686	85 / <mark>38.6</mark>	-	76 / <mark>35</mark>	-
3	13.13 / 334	18.75 / <mark>476</mark>	7.94 / <mark>202</mark>	12.00 / 305	6.50 / 165	8.00 / <del>203</del>	1/2	27.00 / 686	-	86 / 39	-	86 / <mark>39</mark>
4	16.75 / <mark>425</mark>	19.88 / <del>505</del>	10.75 / <mark>273</mark>	10.75 / <mark>273</mark>	9.63 / 245	11.38 / 289	1/2	30.00 / 762	140 / 63.6	-	125 / <del>55</del>	-
4	17.25 / <del>438</del>	19.88 / <del>505</del>	10.69 / 272	10.69 / 272	9.25 / <mark>235</mark>	11.38 / <mark>289</mark>	1/2	30.00 / 762	-	130 / 59	-	130 / 59
5	18.13 / 461	25.13 / <mark>638</mark>	10.75 / <mark>273</mark>	15.25 / <del>387</del>	10.00 / 254	11.38 / 289	1/2	41.00 / 1041	182 / 82.7	-	170 / 775	-
6	19.63 / 499	28.50 / 724	10.69 / 272	18.38 / 467	10.00 / <mark>254</mark>	11.38 / <mark>289</mark>	1/2	46.00 / 1168	270 / 122.7	235 / 107	200 / 91	235 / 107
8	27.00 / 686	40.50 / 1029	-	27.00 / 686	13.75 / 349	17.50 / <b>445</b>	1/2	60.00 / 1524	600 / 272.7	550 / <mark>250</mark>	500 / <mark>227</mark>	550 / <mark>250</mark>

# Click Here For Your Free Quote






## TECHNICAL INFORMATION


Standard Cast Pipeline Strainers

## Basket and Screen Data


## Pattern Examples




Staggered Holes Straight Holes




1/32" - Actual Size



1/16" – Actual Size



1/8" - Actual Size



1/4" - Actual Size

## **Basket and Screen Design**

Designed to be both effective and durable, the basket or screen is the heart of an Eaton strainer. Eaton supplies baskets for simplex and duplex strainers, and screens for Y strainers, in standard and heavy-duty designs. Standard design baskets meet the needs of most applications. Eaton recommends the heavy-duty design in cases when straining an extremely high viscosity material or experiencing a high solids load.

Eaton baskets and screens are available in two standard materials: 316 stainless steel or Monel. These materials cover nearly all corrosion resistance levels needed in strainer services. A wide range of perforations and mesh provides removal of solids from 1/2" down to as low as 40 microns. For special, unique applications, Eaton custom fabricates baskets from just about any material to exact specifications.

## **Basket Construction**

Each style basket includes a perforated sheet induction welded to a rigid top ring and solid bottom cap. Special attention to the welds along the perforated sheet seam, prevent the possible bypass of solids and maintain the basket's strength. A handle, welded to the I.D. of the top ring, facilitates easy removal. Heavy-duty baskets have reinforcing strips induction welded along the perforation's

seam, and circumferentially on the outside of the mid-section of the basket. The perforated sheet is inside the top ring and bottom cap.

### **Screen Construction**

Y strainer screens, rolled to form a perfect cylinder, are induction welded along the seam. A neat weld, applied along the perforated sheet seam, prevents the possible bypass of solids and provides a seam of acceptable strength. Eaton machines Y strainer screen seats to specific dimensions and, accordingly, both the O.D. and length of these screens are closely toleranced.

## Perforated Sheet – Specification

Eaton baskets utilize perforated sheets because of their greater inherent strength and resistance to stress cracking. The percentage of open area of a screen generally dictates the internal pressure drop experienced across it. The objective is to select a perforation with the best balance of open area, hole arrangement, and sheet thickness.

## Open Area

Perforated sheets can have an open area from 15% to 75%. In general, the larger the open area of perforated sheet, the thinner the sheet thickness must be. Holes punched closer together increase the perforated open area; the solid portion between holes distorts

and becomes weak. Another factor in controlling the sheet thickness is the hole diameter. The smaller the hole diameter, the thinner the sheet. The rule of thumb used by commercial perforated sheet manufacturers is that hole dimensions smaller than the plate thickness are impractical and costly to manufacture. Eaton baskets and screens have between 28% to 63% open area with gauge thickness from 18" (0.048") to 25" (0.021"), depending upon the size of the perforations and the size and model of the strainer.

## **Hole Arrangement**

Holes can be punched either in a straight line or in a staggered pattern. Eaton baskets and screens have a staggered pattern that increases the open area, provides extra strength, and creates less pressure drop.

#### **Perforations**

Eaton baskets and screens are available in 1/32", 3/64", 1/16", 1/8", 5/32", 1/4", 3/8", and 1/2" perforations and in mesh sizes 20, 40, 60, 80, 100, 200, 325, and 400. However, for general service there is one perforation for each size and type of strainer. Unless specified, this standard perforation is the size furnished with the strainer.



## TECHNICAL INFORMATION

Standard Cast Pipeline Strainers

## Basket and Screen Data

#### Wire Mesh Specifications

All Eaton strainers are available with woven wire mesh screens. Wire mesh provides smaller openings for very fine straining applications down to 40 microns. Eaton baskets and screens use monofilament mesh possessing equal wire size and wire count in both directions to produce square openings. Other types of mesh such as Dutch (or Hollander) are also available. Dutch weave has a greater quantity of wires in one direction and fewer wires of a larger diameter in the other direction. This creates a rectangular opening. As with perforated sheet, the best wire mesh selection is a balance of open area, wire diameter, and type of weave.

## **Openings**

Standard wire mesh liners for Eaton baskets and screens are available from 20 to 400 mesh. For any size mesh, there are different open area selections based on the diameter of the wires used. Twenty mesh means 20 wires per inch in both a vertical and horizontal direction. Therefore, as the wire size increases, the hole size decreases. Eaton baskets offer wire mesh with openings from 0.034" to 0.0015" (20 mesh to 400 mesh).

## Open Area

The open area of wire mesh is a function of both the weave and the wire diameter. Eaton uses a plain square weave in most cases because its straight-through flow path creates the least pressure drop. The mesh is

reinforced with a perforated metal backing possessing greater than a 60% open area. This combination affords the greatest degree of strength, yet offers a lower pressure drop than other types of wire mesh. In certain instances, such as Y strainer in steam applications, the increased pressure drop resulting from the use of a Dutch weave is not as critical as the retention of small particles. Therefore, in applications that involve steam, Eaton suggests the use of weave such as the 30 x 160 size that can withstand a much higher differential pressure without bursting. Eaton can supply baskets and screens with open areas from 14% to 46%

## **Plain Square Weave**

Woven in an over and under pattern of wire having the same diameter, this weave produces a square opening with excellent flow characteristics.

## **Plain Dutch Weave**

Woven in an over and under pattern in one direction in which the horizontal wires are larger in diameter than the vertical wires, which are driven close and crimped at each pass. This weave produces greater strength, but lower flow rates, than a square weave. Most often used in steam applications.

#### Mesh Liners Available

The number of openings per linear inch determines the size of mesh liners. The standard sizes Eaton can furnish are 20, 40, 60, 80, 100, 200, 325, and 400.


## **Perforated Basket Sheet Specifications**

Perforation Size Inches	Sheet Thickness USS Gauge #	Hole Pattern	% Open Area
0.020	26	Straight	16.0
1/32	26	Straight	28.0
3/64	26	Straight	30.2
0.045	26	Staggered	36.0
1/16	26	Straight	31.0
1/8	26	Staggered	47.9
5/32	26	Staggered	63.0
1/4	26	Staggered	42.0
3/8	26	Staggered	52.0
1/2	26	Staggered	47.9


## Mesh Basket Sheet Specifications

Mesh Size	Wire Diameter Inches	Mesh Opening Inches	Mesh Opening Microns	% Open Area
20	0.016	0.0340	864	46.2
40	0.010	0.0150	381	36.0
60	0.0075	0.0092	234	30.5
80	0.0060	0.0065	165	27.0
100	0.0045	0.0055	140	30.3
200	0.0021	0.0029	74	33.6
325	0.0014	0.0017	43	30.0
400	0.0015	0.0381	38	36.0

#### Wire Mesh Weaves



Plain Square Weave



**Plain Dutch Weave** 





# TECHNICAL INFORMATION Standard Cast Pipeline Strainers

## Basket Effective Area

Strainer Model	Pipe Size	Perforation Size	Nominal Area of Pipe (sq in)	Gross Screen Area (sq in)	Free Area (sq in)	Ratio Free Area to Pipe Area
85	1/4	.045	.10	5.0	1.8	18.0
85	3/8	.045	.19	5.0	1.8	9.5
85	1/2	.045	.30	5.0	1.8	6.0
85	3/4	.045	.53	7.1	2.6	4.9
85	1	.045	.86	10.4	3.7	4.3
85	1-1/4	.045	1.49	15.1	5.5	3.7
85	1-1/2	.045	2.03	21.7	7.8	3.8
85	2	.045	3.35	30.4	10.9	3.3
85	2-1/2	.045	4.78	43.2	15.5	3.2
85	3	.045	7.39	70.7	25.5	3.4
85	4	.045	12.73	106.8	38.4	3.0
85	6	.045	28.70	241.7	87.0	3.0
85	8	.045	50.02	414.6	149.2	3.0
85	10	.045	71.80	652.2	234.8	3.3
30R	1-1/2	5/32	2.03	35.4	22.3	11.0
30R	2	5/32	3.35	50.9	32.1	9.6
30R	2-1/2	5/32	4.78	84.7	53.4	11.2
30R	3	5/32	7.39	84.7	53.4	7.2
30R	4	5/32	12.73	114.5	72.1	5.6
30R	5	5/32	20.0	158.1	99.6	5.0
30R	6	5/32	28.9	180.9	113.9	4.0
30R	8	5/32	50.03	275.6	171.8	3.4
50	3/4	1/32	0.53	19.5	5.2	9.8
50	1	1/32	0.86	19.5	5.2	6.1
50	1-1/4	1/8	1.49	39.7	19.0	12.8
50	1-1/2	1/8	2.03	39.7	19.0	9.4
50	2	1/8	3.35	64.0	30.7	9.2
50	2 -1/2	1/8	4.78	64.0	30.7	6.4
50	3	3/16	7.39	85.6	42.8	5.8
50	4	3/16	12.73	146.1	73.0	5.7
50	5	3/16	20.0	216.1	106.0	5.4
50	6	3/16	28.9	265.4	132.7	4.6
50	8	3/16	50.02	506.7	253.4	5.1
50	10	3/16	78.8	800	400	5.1
50	12	3.16	113,1	1200	600	5.3
50	14	3/16	137.9	2000	1000	7.3
50	16	3/16	182.6	2000	1000	5.5
50	18	3/16	182.6	2000	1000	5.5
53BTX	3/4	1/32	0.53	19.8	5.5	10.4
53BTX	1	1/32	0.86	19.8	5.5	6.4
53BTX	1-1/4	1/8	1.49	45.0	22.0	14.4
53BTX	1-1/2	1/8	2.03	45.0	22.0	10.6
53BTX	2	1/8	3.35	65.0	31.0	9.3
53BTX	2 -1/2	1/8	4.78	65.0	31.0	6.5
53BTX	3	3/16	7.39	110.3	55.1	7.4
53BTX	4	3/16	12.73	152.0	76.0	5.9

Strainer Model	Pipe Size	Perforation Size	Nominal Area of Pipe (sq in)	Gross Screen Area (sq in)	Free Area (sq in)	Ratio Free Area to Pipe Area
72	3/8	1/32	0.19	12.7	3.4	18.0
72	1/2	1/32	0.30	12.7	3.4	11.3
72	3/4	1/32	0.53	19.5	5.2	9.9
72	1	1/32	0.86	19.5	5.2	6.1
72	1-1/4	1/8	1.49	30.1	14.4	9.7
72	1-1/2	1/8	2.03	49.7	19.0	9.4
72	2	1/8	3.35	50.9	24.4	7.3
72	2-1/2	1/8	4.78	80.2	38.4	8.0
72	3	3/16	7.39	114.5	57.2	7.8
72	4	3/16	12.73	168.3	84.1	6.6
72	5	3.16	20.0	265.4	132.7	6.6
72	6	3/16	28.9	324.2	162.1	5.6
72	8	3/16	50.02	555.3	277.7	5.6
72	10	3/16	78.8	800	400	5.1
72	12	3/16	113.1	1200	600	5.3
72	14	3/16	137.9	2000	1000	7.3
72	16	3/16	182.6	2000	1000	5.5
72	18	3/16	182.6	2000	1000	5.5

## Alloy Data

## Metal Alloys used in Eaton Strainers

## Aluminum Bronze – ASTM B-148 Grade C95400

Tensile Strength: 75,000 lb/sq in	
Yield:	
Elongation: 12%	
Chemical Composition:	
Cu (Copper)85%	
Fe (Iron)4%	
Al (Aluminum) 11 %	

## Stainless Steel - ASTM A-351 Grade CF8M

Yield:30,000 lb/sq ir
Elongation: 30%
Chemical Composition:
C (Carbon) 0.08% max
Si (Silicon) 1.5%
P (Phosphorus) 0.040%
Cr (Chromium) 18.0 - 21.0%
Ni (Nickel) 9.0 - 12.0%
Mn (Manganese) 1.50%
S (Sulfur) 0.04%
Mo (Molybdenum) 2.0 - 3.0%

Tensile Strength: . . . . . . 70,000 lb/sq in

## Cast Iron - ASTM A-126 Class B Tensile Strength: . . . . 31,000 lb/sq in

Compressive Strength:	109,000 lbs/sq in
Tensile Modulus:	15 x 10 <sup>6</sup> lb/sq in
Chemical Composition:	
C (Carbon)	3.20 - 3.40 %
Si (Silicon)	2.10 - 2.30%
P (Phosphorus)	0.15 - 0.30%
S (Sulfur)	0.08 - 0.12%

Mn (Manganese) ... 0.50 - 0.80%

Tensile Strength: . . . . 60,000 lb/sq in

## Ductile Iron - ASTM A-395 Grade 60-40-18

Yield:	40,000 lb/sq i
Elongation:	18%
Chemical Composition:	
C (Carbon)	3.20 - 4.0%
Si (Silicon)	1.80 - 2.80%
P (Phosphorus)	0.08% max.
S (Sulfur)	0.03% max.
Mn (Manganese)	0.03% max.



## TECHNICAL INFORMATION Standard Cast Pipeline Strainers

## Pressure Drop Calculations

Pressure drops for Eaton strainers are shown on each product page. The curves are based on the flow of water through clean, perforated baskets or screens. For mesh-lined baskets or screens and/or for fluids other than water, use the correction factors listed on this page. To accurately calculate the pressure loss for filters and strainers in a pipeline, proceed as follows:

- 1. First calculate pressure loss using C<sub>V</sub> factor formula at right.
- 2. Take the pressure loss figure obtained in (1) and recalculate it using the appropriate correction factor from the following table.

## Correction Factors for Mesh-Lined Baskets

First - Multiply the pressure drop for water shown in charts by the specific gravity of the liquid.

**Second** – Multiply the corrected pressure drop figure by the following correction factors for more viscous liquids. (Water has a viscosity of 30 SSU.)

Viscosity (SSU)	Unlined Perforated Basket	40 Mesh Lined Basket	60 Mesh Lined Basket	80 Mesh Lined Basket	100 Mesh Lined Basket	200 Mesh Lined Basket	325 Mesh Lined Basket
30 (water)	0	1.2	1.4	1.6	1.7	2.0	2.5
500	1.6	1.9	2.1	2.4	2.6	3.1	3.6
1000	1.7	2.2	2.4	2.6	2.8	3.3	3.8
2000	1.9	2.4	2.7	2.9	3.2	3.8	4.0
3000	2.0	2.6	2.9	3.2	3.5	4.1	4.3
5000	2.2	3.0	3.5	4.0	4.5	5.3	6.3
10000	2.5	3.5	4.2	5.0	6.0	7.1	8.5

## Strainer Basket Opening Equivalents

			0 1				
Mesh	Inches	Millimeters	Microns	Perf	Inches	Millimeters	Microns
400	0.0015	0.0381	38	1/32	0.033	0.838	838
300	0.0018	0.0457	45	3/64	0.045	1.143	1143
250	0.0024	0.0609	60	1/16	0.070	1.778	1776
200	0.0027	0.0686	68	3/32	0.094	2.387	2387
150	0.0041	0.1041	104	1/8	0.125	3.175	3175
100	0.0065	0.1651	165	5/32	0.150	3.810	3810
80	0.007	0.1778	177	3/16	0.1875	4.762	4762
60	0.009	0.2286	228	1/4	0.250	6.350	6350
40	0.015	0.8636	380	3/8	0.375	9.525	9525
20	0.034	0.8636	862	1/2	0.500	12.700	12700

## Pressure Loss Calculation Using C<sub>V</sub> Factor

## **Metric Units**

$$\Delta P = \left[\frac{Q}{C_{v}}\right]^{2} (133.6)$$

 $\Delta P$  = Pressure Drop in kPa

Q = Flow in M<sup>3</sup>/hr

C<sub>V</sub> = Flow Coefficient

## **Standard Units**

$$\Delta P = \left[\frac{Q}{C_V}\right]^2$$


 $\Delta P$  = Pressure Drop in psi

Q = Flow in qpm


C<sub>V</sub> = Flow Coefficient

The pressure loss across a strainer can be calculated using the system's flow rate and the C<sub>V</sub> factor for that strainer.

For example, a 1" Model 72 simplex strainer with a perforated basket has a C<sub>V</sub> factor of 22.5. In water service with a 30 gpm flow rate, it will have a 1.7 psi pressure drop  $(30 \div 22.5)^2 = 1.7$ . For mesh-lined baskets and/or fluids with a viscosity greater than water, multiply the pressure drop by the correction factors in the chart "Correction Factors for mesh-lined baskets."



**CLICK HERE FOR** CALCULATOR



	REVISIONS										
REV	DESCRIPTION	BY	ECO	DATE							
G	UPDATED TITLE BLOCK	R. DHONDE	0106104	12/25/2014							

N□.	PART NAME	MATERIAL							
1	B□DY	CAST IRON ASTM A126 CL B							
2	SCREEN								
	PERF. DIA.								
	MESH								
3	C□VER	CAST IRON ASTM A126 CL B							
4	YOKE	DUCTILE IRON							
5	YOKE SCREW	STEEL							
6	□-RING	BUNA-N							
7	STUD	STEEL							
8	PIPE PLUG	CAST IRON							

### NOTES:

- 1. INLET/DUTLET "NPT" THREADED CONNECTIONS PER ASME B1.20.1.
- 2. MAX. WORKING PRESSURE: 200 PSI @ 100° F (13.8 BAR @ 37.8° C)
- 3. 1/2" STRAINER WITH REDUCER BUSHING.


# Click Here For Your Free Quote

PIPE SIZE				DIMENSIC	]NS			WEIGHT	
(NOMINAL)	IN. MM.	· · ·		D IN. MM.	F IN. MM.	G (N□M.) IN. MM.	H IN. MM.	(DRY) LBS, KGS,	PART NO.
*3/8" (10mm)	4.75 / 121	IN. MM. 6,63 / 168	IN. MM. 2.88 / 73	IN. MM. 4.00 / 102	IN. MM.	3/8 (10)	2.50 (64)	4 / 1.8	ST0720037T4C
*37.0 (101/11/17	4./3 / 161	0,03 / 100	2.00 / /3	4.00 / 102	11 / [//	376 (107	` ′	4 / 1.0	310/2003/140
1/2" (15mm)	4.00 / 102	6.63 / 168	2.88 / 73	4.00 / 102	11 / 279	3/8 (10)	2.18 (54)	4 / 1.8	ST0720050T4C
3/4" (20mm)	5.38 / 137	8.38 / 213	4.00 / 102	5.00 / 127	13 / 330	1/2 (15)	3.13 (80)	7 / 3.2	ST0720075T4C
1" (25mm)	5.38 / 137	8.38 / 213	4.00 / 102	5.00 / 127	13 / 330	1/2 (15)	3.13 (80)	7 / 3.2	ST0720100T4C
1-1/4" (32mm)	6.75 / 172	9.88 / 251	4.88 / 124	5.88 / 149	14 / 356	1/2 (15)	3.75 (95)	12 / 5.5	ST0720125T4C
1-1/2" (40mm)	7.38 / 187	11.00 / 279	4.88 / 124	7.00 / 178	16 / 406	3/4 (20)	4.17 (106)	15 / 6.8	ST0720150T4C
2" (50mm)	8.75 / 222	13.38 / 340	6.75 / 172	7.63 / 194	21 / 533	1-1/4 (32)	5.13 (130)	28 / 12.7	ST0720200T4C
2-1/2" (65mm)	10.50 / 267	14.88 / 378	8.00 / 203	8.88 / 226	26 / 660	1-1/2 (40)	6.19 (157)	42 / 19.1	ST0720250T4C
3" (80mm)	11.63 / 295	17.75 / 451	8.00 / 203	11.50 / 292	28 / 711	1-1/2 (40)	6.75 (171)	52 / 23.6	ST0720300T4C

\* - SEE NOTE 3

		DRAWN BY	LIVED							
		SCALE AS DRAWN		G,	HYDRAULICS GROUP FILTRATION DIVISI ALESBURG, MICHIGAN, USA • TINTON FALLS, NEW JERSI	O N EY, USA				
С	USTOMERINFO	RESTRICTED	TITLE MODEL 72 SIMPLEX STRAINER NPT THREADED							
NAME		SHEET	CONNECTIONS SIZES 3/8" THRU 3" CAST IRC							
P.O. NO.		1 OF 1								
1 101 1101		PROJECTION	DATE	SIZE	DWG FILENAME	REV				
TAG NO.		THIRD ANGLE \$\Psi\$	08/21/91	A	SD072014	<u> </u> G				
S.O. NO.		THIS DOCUMENT, INCLUDING THE DRAWING AND INF POSSESSION OF THIS DOCUMENT THE RECIPIENT ACK	ORMATION CONTAINED THEREON IS NOWLEDGES AND AGREES THAT THIS	CONFIDENT DOCUMEN	IS RECEIVING THIS DRAWING AND/OR TECHNICAL INFORMATION TAND IS THE EXCLUSIVE PROPERTY OF EATON AT ANY TIME. BY TAKIN NT CANNOT BE USED IN ANY MANNER ADVERSE TO THE INTEREST OF EA	TON AND				
PART NO.	SEE TABLE	THAT NO PORTION OF THIS DRAWING MAY BE COPIED OR OTHERWISE REPRODUCED WITHOUT THE PRIOR WRITTEN CONSENT OF EATON, IN THE CASE OF CONFLICTING CONTRACTUAL PROVISIONS, THIS NOTICE SHALL GOVERN THE STATUS OF THIS DOCUMENT.  2015 EATON CORPORATION – ALL RIGHTS RESERVED.								

	REVISIONS			
REV	DESCRIPTION	BY	ECO	DATE
J	UPDATED TITLE BLOCK	R. DHONDE	0106104	12/25/2014



N□.	PART NAME	MATERIAL							
1	B□DY	CAST IRON ASTM A126 CL.B							
2	SCREEN								
	PERF. DIA.								
	MESH								
3	COVER	CAST IRON ASTM A126 CL.B							
4	YOKE	DUCTILE IRON							
5	YOKE SCREW	STEEL							
6	□-RING	BUNA-N							
7	DUTS	STEEL							
8	DRAIN PLUG	CARBON STEEL							
9	BODY PLUG	CAST IRON							
10	COVER CLAMP	DUCTILE IRON							


- 1. INLET/DUTLET 125 LB. FLANGED CONNECTIONS PER ASME B16.1.
- 2. COVER CLAMP (ITEM 10) FOR 4", 5", 6" SIZES. 3. NO FOOT PADS FOR SIZES 1", 1-1/4", 1-1/2".
- 4. 7/16"Ø SLOTTED FOOT PADS FOR SIZE 2".
- 5. 1/2"Ø SLOTTED FOOT PADS FOR SIZES 2-1/2",3".
- 6. 9/16"Ø HOLED FOOT PADS FOR SIZES 4",5",6".
- 7. DIMENSIONS B,D,F ARE FROM BOTTOM OF STRAINER.
- 8. DIMENSION "G" (NPT) IS FOR DRAIN PLUG, ITEM 8. 9. ITEM 9, BODY PLUG IS NOT TO BE USED AS DRAIN.
- 10. MAX. WORKING PRESSURE : 200 PSI @ 100° F
- (13.8 BAR @ 37.8° C)
- 11. 1 1/4" NPT STRAINER WITH CLOSE NIPPLES AND THREADED FLANGES

## Click Here For Your Free Quote

PIPE	SIZE								DIM	1EN	SIO	NS					WEIG	ΞΗТ	
(NIDM	(INAL)	A	4	l I	3	(	)	D			F	G (1	(.M□I	Н	J	К	(DR)	Y)	PART NO.
(IADI.	IIINHL7	IN.	MM.	IN.	MM.	IN.	MM.	IN.	MM.	IN.	MM.	IN.	MM.	IN. MM.	IN. MM.	IN. MM.	LBS	KGS	
1"	(25mm)	7.63/	194	8.38/	213	4.00/	102	5.00/	127	13/	330	1/2	(15)			4.31/ 109	9/	4	ST072010AF40A
*1-1/4	" (32mm)	10.25/	260	9.88/	251	4.88/	124	5.88/	149	14/	356	1/2	(15)			5.63/ 143	13/	6	ST072012AF40A
1-1/2"	(40mm)	10.25/	260	11.00/	279	4.88/	124	7.00/	178	16/	406	3/4	(20)			5.63/ 143	17/	8	ST072015AF40A
2"	(50mm)	10.50/	268	13.75/	349	6.75/	172	7.63/	194	20/	508	1/2	(15)	5.50/140	2.50/ 64	6.13/ 156	37/	17	ST0720200F4C
2-1/2*	(65mm)	11.63/	295	15.63/	′ 397	7.94/	202	8.88/	226	23/	584	3/8	(10)	6.50/165	2.88/ 73	6.63/ 168	54/	24	ST0720250F4C
3"	(80mm)	13.13/	334	18.00/	457	8.00/	203	10.88/	276	27/	686	3/8	(10)	7.00/178	3.13/ 80	7.13/ 181	76/	34	ST0720300F4C
4"	(100mm)	16.75/	425	19.88/	′ 505	10.69/	272	10.69/	272	29/	737	1/2	(15)	10.00/254	3.88/ 99	9.38/ 238	125/	57	ST0720400F4C
5″	(125mm)	18.13/	460	25.13/	638	10.69/	272	15.19/	386	38/	965	1/2	(15)	10.00/254	4.63/118	10.13/ 257	170/	77	ST0720500F4C
6"	(150mm)	19.63/	499	28.50/	724	10.69/	272	18.31/	465	46/	1168	1/2	(15)	10.00/254	5.00/127	10.81/ 275	200/	91	ST0720600F4C
1																			

* - SEE	NOTE 11								
		DRAWN BY			HYDRAULICS GROUP FILTRATION DIVISI	O N			
		SCALE AS DRAWN		ALESBURG, MICHIGAN, USA • TINTON FALLS, NEW JERSE	O N EY, USA				
С	USTOMERINFO	RESTRICTION RESTRICTED	TITLE   MODEL 72 SIMPLEX STRAINER 125# FLAT						
NAME		SHEET	FACE FLANGE, SIZES 1" THRU 6" CAST IRON						
P.O. NO.		PROJECTION	DATE	DWG FILENAME	REV				
TAG NO.		THIRD ANGLE	11/26/91	size A	SD072024	J			
S.O. NO.		EATON CORPORATION — CONFIDENTIAL AND PROPRIETARY NOTICE TO PERSONS RECEIVING THIS DRAWING AND/OR TECHNICAL INFORMATION THIS DOCUMENT, INCLUDING THE DRAWING AND INFORMATION CONTAINED THEREON IS CONFIDENTIAL AND IS THE EXCLUSIVE PROPERTY OF EATON AT ANY TIME. BY TAKING THE POSSESSION OF THIS DOCUMENT THE RECPIENT ACKNOWLEDGES AND AGREES THAT THIS DOCUMENT CANNOT BE USED IN ANY MANNER ADVERSE TO THE INTEREST OF EATON AND							
PART NO.	SEE TABLE	THAT NO PORTION OF THIS DRAWING MAY BE COPIE	PIED OR OTHERWISE REPRODUCED WITHOUT THE PRIOR WRITTEN CONSENT OF EATON, IN THE CASE OF CONFLICTING CONTRACTUA PROVISIONS, THIS NOTICE SHALL GOVERN THE STATUS OF THIS DOCUMENT. 2015 EATON CORPORATION — ALL RIGHTS RESERVED.						

REVISIONS									
REV	DESCRIPTION	BY	ECO	DATE					
В	UPDATED TITLE BLOCK	R. DHONDE	0106104	12/25/2014					



PIPE SIZE

N□.	PART NAME	MATERIAL				
1	B□DY	CAST IRON ASTM A126 CL.B				
2	SCREEN					
	PERF. DIA.					
	MESH					
3	COVER	CAST IRON ASTM A126 CL.B				
4	YOKE	DUCTILE IRON				
5	YOKE SCREW	STEEL				
6	O-RING	BUNA-N				
7	STUD	STEEL				
8	DRAIN PLUG	CARBON STEEL				
9	BODY PLUG	CAST IRON				

## NOTES:

- 1. INLET/OUTLET 125 LB. FLAT FACED FLANGED CONNECTIONS PER ASME B16.1.
- 2. 5/8" DIAMETER SLOTTED FOOT PADS FOR 8" SIZE.
- 3. DIMENSION "G" (NPT) IS FOR DRAIN PLUG, ITEM 8.
- 4. ITEM 9, BODY PLUG IS NOT TO BE USED AS DRAIN. 5. MAX. WORKING PRESSURE: 200 PSI @ 100° F
  - (13.8 BAR @ 37.8° C)

Click Here
For Your Free Quote

WEIGHT


(NOMINAL)	A	В	С	D F		G (N□M.)		Н	J	(DRY)	PART	NΠ
	IN. MM.	IN. MM.	IN. MM.	IN. MM.	IN.	MM.	IN. MM.	IN. MM.	IN. MM.	LBS. KGS.		. ,
8" (200mm	27.00 / 686	40.00 /1016	15.50 /394	27.00 / 686	60 /1	.524	1-1/2 (40)	15.75 /4	00 8.63 /219	500/ 227	ST0720800	DF4C
				DRAWN BY J. JOHNSON			HYDRAULICS GROUP FILTRATION DIVISION					
			SCALE AS DRA	J. JOHNSON  SCALE  AS DRAWN  HYDR.  GALESBURG, MICHIGAN, L			SA • TINTON FAL					
I				ESTRICTION TITLE  RESTRICTED MODEL 72 SIMPLEX STRAINER, 125# FLA			FLAT					
NAME	NAME SHEET 1 OF 1			FACE FLANGE, SIZE 8" CAST IRON								
P.O. NO.			PROJECTION			DATE		SIZE DW	G FILENAME			REV
TAG NO.			THIRD AI				0/11/13	A		072038		В
S.O. NO.			EATON CORPORATION — CONFIDENTIAL AND PROPRIETARY NOTICE TO PERSONS RECEIVING THIS DRAWING AND/OR TECHNICAL INFORMATION THIS DOCUMENT, INCLUDING THE DRAWING AND INFORMATION CONTRINED THEREON IS CONFIDENTIAL AND IS THE EXECULISVE PROPERTY OF EATON AT ANY TIME. BY TAKING THE POSSESSION OF THIS DOCUMENT THE RECIPIENT ACKNOWLEDGES AND AGREES THAT THIS DOCUMENT CANNOT BE USED IN, ANY MANNER ADVERSE TO THE INTEREST OF EATON AND						ATON AND			
PART NO.	SEE TA	ABLE	THAT NO PORTION OF THIS DRAWING MAY BE COPIED OR OTHERWISE REPRODUCED WITHOUT THE PRIOR WRITTEN CONSENT OF EATON, IN THE CASE OF CONFLICTING CONTRACTUAL PROVISIONS, THIS NOTICE SHALL GOVERN THE STATUS OF THIS DOCUMENT.  2015 EATON CORPORATION - ALL RIGHTS RESERVED.					KACIUAL				

DIMENSIONS



## Installation, Operation & Maintenance Manual Model 72 Simplex Basket Strainer, Sizes 3/8" - 8"

Read all the following information and instructions prior to installing and operating the equipment. Failure to comply with these instructions could result in bodily injury or property damage.



## **TABLE OF CONTENTS**

Dago No

	rage No.
Introduction	1
Receiving, Handling & Inspection	2
Installation	2
Operation	3
Shut-Down	3
Basket Removal	3
Basket Replacement	4
Basket Cleaning	4
Recommended Spare Parts	4
Exploded Parts Drawing	Δ

## INTRODUCTION

A simplex strainer is a device installed in a pipeline to remove dirt and other unwanted debris from fluids. Straining is accomplished by directing the fluid through sized openings in a basket. Simplex strainers are installed where fluid flow can be interrupted while the basket is removed for cleaning. Simplex strainers are designed to withstand the rated pressure of the piping system.

For additional information regarding Simplex Basket Strainers visit our website at www.eaton.com/filtration



## Installation, Operation & Maintenance Manual Model 72 Simplex Basket Strainer, Sizes 3/8" - 8"

## RECEIVING, HANDLING, AND INSPECTION

Inspect strainer after unpacking for damage incurred during transit. Report any damage to the carrier immediately. If the strainer is not to be installed immediately, store indoors in a clean, dry environment.

Remove preservative with a solvent dampened cloth. Exercise care when using solvent.

#### Model 72 Simplex

Size	Material	<b>End Connection</b>	Seals	<b>Pressure Rating</b>
3/8" to 3"	Iron and Bronze	Threaded	Buna-N	200 psi @ 100°F
1" to 3"	Carbon Steel	Threaded	Buna-N	200 psi @ 100°F
1" to 3"	Stainless Steel	Threaded	Viton®	200 psi @ 100°F
1" to 8"	Iron	Flanged 125#	Buna-N	200 psi @ 100°F
1" to 8"	Bronze	Flanged 150#	Buna-N	200 psi @ 100°F
1" to 8"	Carbon Steel	Flanged 150#	Buna-N	200 psi @ 100°F
1" to 8"	Stainless Steel	Flanged 150#	Viton®	200 psi @ 100°F

Check to be sure the rated pressure and temperature on the strainer nameplate is not less than the maximum pressure and temperature of the installation. The rated pressure shown on the nameplate is the maximum pressure, including shock, at which the strainer may be operated.

Remove cover by turning T-bolt counterclockwise to release yoke, swing yoke clear of cover and remove cover. Check for and remove any foreign or loose materials that could be carried downstream when fluid is introduced into the strainer.

Replace strainer cover and yoke and tighten T-bolt. The basket is held in place by pressure of the cover on the basket handle. If the basket is loose, spring the handle to a higher position to insure greater compression when the cover is seated.

## **INSTALLATION**

Position the strainer in the line so that the fluid enters the connection marked "inlet."



**CAUTION:** Lift strainers with slings under the inlet and outlet connections. DO NOT lift the strainer by the yoke screw located on the strainer cover.

Be sure sufficient headroom is provided for easy removal of cover and basket.

Support the strainer in the line as follows:

#### 4" size or under:

Use pipe supports under the process piping near inlet and outlet connections. Use care to prevent bending and expansion forces from acting on the nozzles.

## 5" size or larger:

Support on concrete or steel pads.

Connect the strainer to the line. Use same type flange faces. For example: **Do not** bolt raised face flanges to iron flat face flanges. Iron flanges must be flat face with full face gaskets.

Cast strainers are subject to face-to-face variations due to shrinkage and machining tolerances.

Prefabricated piping systems must allow adjustment at the strainer connection.

If strainer has threaded connections follow proper threaded specifications. If strainer has weld connection follow proper ANSI weld specifications.

Be sure flange gaskets are in place and fasteners are tight.



## Installation, Operation & Maintenance Manual Model 72 Simplex Basket Strainer, Sizes 3/8" - 8"

## **INSTALLATION** (CONTINUED)

It is recommended that the bottom drain plug be removed and a drain valve be installed at the bottom of the basket chamber for strainers sized 1" and 1-1/2" flanged connections and for strainers sized 3/8" - 3" threaded connections. It is recommended that the side drain plug be removed and a drain valve be installed at the side of the basket chamber for strainers sized 2" – 8" flanged connections as shown in Fig. 1.




**CAUTION:** The bottom plug for flanged strainers, sized 2" through 8" is NOT to be removed and the opening NOT to be used for draining. Removal of this bottom plug voids the strainer warranty.



CAUTION: A vent is required when fluids other than water and with temperatures in excess of 120° F are to be handled by the strainer. The vent must be piped to a safe discharge point to protect

the operator. (See Fig.2). Wear protective clothing, which includes gloves, vests, and goggles when handling dangerous fluids.

Pressure gauges near the strainer inlet and outlet are recommended. Cleaning frequency is determined by the pressure drop across the strainer.



## **OPERATION**

Open vent, if strainer is so equipped (See Fig. 2), to expel air from the strainer.

Slowly introduce fluid to be strained by opening the outlet valve first, followed by opening the inlet valve.



CAUTION: Start system GRADUALLY. This eliminates sudden shock to the strainer and other equipment in the line.

Close the vent when air is expelled and fluid begins to flow.

## **SHUT-DOWN**

Tightly close valves on the inlet and outlet connections or the strainer. Open vent (See Fig. 2) and/or drain valve (See Fig.1) to relieve liquid pressure in the strainer.



**CAUTION:** DO NOT loosen cover while there is liquid or air flow from the vent.

## **BASKET REMOVAL**

Follow shut-down procedure.

When pressure is relieved, loosen T-bolt. Drain fluid through bottom drain to a level below the basket seat.

Swing yoke clear of cover and remove cover and dirty basket.



# Installation, Operation & Maintenance Manual Model 72 Simplex Basket Strainer, Sizes 3/8" - 8"

## **BASKET REPLACEMENT**

Place new or clean basket squarely on the basket seat. Be sure basket handle is sufficiently high to be compressed by strainer cover.

Inspect 0-ring and seal surface: Clean seat or replace cover 0-ring as necessary. Always keep spare 0-rings in stock.

Replace cover, swing the yoke over the cover and make full contact with the yoke stud. Tighten the center T-bolt. If strainer is on suction service, fill basket chamber from outside source before installing cover.

Follow start-up procedure.

## **BASKET CLEANING**

#### When to Clean

Clean basket when there is a 5 psi increase in pressure loss across the strainer.



**CAUTION:** To prevent damage to basket, DO NOT permit strainer pressure differential between inlet and outlet connections to exceed 20 psi.

## **How to Clean**

Invert basket and wash out debris by directing a stream of air or water against the basket exterior. Use solvent if strained fluid is fuel or a chemical. Follow manufacturer's instruction when using a solvent to clean the basket.



**NOTE**: Do not allow basket contents to dry as this will make cleaning most difficult.

**Inspect** basket at each cleaning for **holes** or tears and replace as required.

# Click Here For Your Free Quote

## **SHUT-DOWN PERIODS**

During shut-down periods drain the fluid and clean the basket.


## RECOMMENDED SPARE PARTS

- 1 Eaton Replacement Basket
- 1 Eaton Replacement 0-Ring

When ordering spare parts, specify all nameplate data as well as the description and quantity of parts.

Always use genuine **Eaton** replacement parts for guaranteed fit and performance.

Visit our web site, www.filtration.eaton.com for information about the hundreds of different types of Eaton Simplex Basket Strainers.



Item	Description
1	YOKE STUD
2	T-BOLT ASSEMBLY
3	YOKE
4	COVER CLAMP
	(sizes 4" to 6" only)
5	COVER
6	O-RING
7	BASKET
8	BODY
9	PIPE PLUG